

DP-1319

662846

# HEAT TRANSFER LABORATORY OF THE SAVANNAH RIVER LABORATORY

D. H. KNOEBEL

S. D. HARRIS

**RECORD  
COPY**

DO NOT RELEASE  
FROM FILE



**E. I. du Pont de Nemours & Co.  
Savannah River Laboratory  
Aiken, S. C. 29801**

PREPARED FOR THE U. S. ATOMIC ENERGY COMMISSION UNDER CONTRACT AT(07-2)-1

## **NOTICE**

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Atomic Energy Commission, nor any of their employees, nor any of their contractors, subcontractors, or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Printed in the United States of America  
Available from  
National Technical Information Service  
U. S. Department of Commerce  
5285 Port Royal Road  
Springfield, Virginia 22151

Price: Printed Copy \$4.00; Microfiche \$0.95

662846

**HEAT TRANSFER LABORATORY  
OF THE SAVANNAH RIVER LABORATORY**

by

D. H. Knoebel

S. D. Harris

Approved by

J. M. Boswell, Research Manager  
Reactor Engineering Division

Publication Date: October 1973

**E. I. du Pont de Nemours & Co.  
Savannah River Laboratory  
Aiken, S. C. 29801**

PREPARED FOR THE U. S. ATOMIC ENERGY COMMISSION UNDER CONTRACT AT(07-2)-1

### ABSTRACT

The Heat Transfer Laboratory, recently constructed adjacent to the main Savannah River Laboratory building, was designed to mock up nuclear heating and cooling of reactor components under a variety of conditions. Nuclear heating is simulated by electrical resistance heating of test sections with a 3 MW direct-current power supply. Cooling is provided by water. Three test stations (A, B, and C) are available for testing full-size fuel assemblies, measuring flow instabilities, and for measuring burn-out heat fluxes. Safeguards provided in the design of the facility and conservative operating procedures minimize or eliminate potential hazards.

## CONTENTS

	<u>Page</u>
Introduction . . . . .	5
Building . . . . .	5
Experimental Test Stations . . . . .	8
Test Station A . . . . .	10
Test Station B . . . . .	12
Test Station C . . . . .	14
Power Supply . . . . .	15
Rectifier Units . . . . .	15
Rectifier Controls . . . . .	17
Cooling Water System . . . . .	18
Instrumentation . . . . .	21
Supporting Services . . . . .	24
Safety . . . . .	24

## LIST OF FIGURES

	Page
1. Heat Transfer Laboratory Building . . . . .	6
2. Floor Plan of Laboratory . . . . .	7
3. Equipment Layout . . . . .	9
4. Test Station A Plan . . . . .	11
5. Test Station A . . . . .	12
6. Test Station B with Test Rig in Place . . . . .	13
7. Test Station C with Test Rig in Place . . . . .	14
8. Rectifier Units . . . . .	15
9. Schematic of Rectifier Circuit . . . . .	16
10. Cross Section of Bus Bars . . . . .	17
11. Process Piping Schematic . . . . .	19
12. Schematic of Piping to a Single Station . . . . .	20
13. Control Console . . . . .	22
14. Recorder Console . . . . .	23

## HEAT TRANSFER LABORATORY OF THE SAVANNAH RIVER LABORATORY

### INTRODUCTION

Several heat transfer laboratories using large DC power supplies and low or high pressure hydraulic loops are in operation in Europe and the Western Hemisphere. Three prominent ones are at Columbia University (8 MW motor generator supply), Battelle Memorial Institute Pacific Northwest Laboratory (1.5 MW rectifier supply and a 3 MW motor-generator supply), and Studsvik Research Establishment in Sweden (8 MW rectifier supply). Previously, the Savannah River Laboratory had a 0.32 MW motor-generator supply and contracted work requiring higher power to Columbia University.

To maintain the necessary high degree of safety in the more complex modes of Savannah River Plant (SRP) reactor operation, the capability of test facilities onsite needed to be expanded to permit experimental investigations associated with flow instability, reactor fuel design, loss-of-target accidents, metal-water corrosion and erosion, and cooling effectiveness during transient conditions. The new Heat Transfer Laboratory was designed to provide these capabilities. The laboratory is located adjacent to the Main Laboratory Building.

### BUILDING

The Heat Transfer Laboratory (Figure 1) and the adjoining electrical substation are prefabricated steel buildings erected on concrete slabs. The substation building contains dry type transformers available from Savannah River Plant excess. The laboratory building is 40 feet wide, 80 feet long, and 24 feet high at the eaves. It is divided into an office area (20 feet long) and an experimental area (60 feet long). Figure 2 is a floor plan of the building.




FIG. 1. HEAT TRANSFER LABORATORY BUILDING






FIG. 2. FLOOR PLAN OF LABORATORY

The experimental area contains all of the experimental equipment (rectifiers, pumps, heat exchangers, piping, test stations, and control console) and a work area for assembling test apparatus. A 12-foot by 12-foot by 57-foot-high loading tower is over one test station at the north end of the building. The tower contains a hoist (1 ton capacity) for manipulating large test sections into the test station vessel. The control console contains all the motor, power, and valve controls and associated instrumentation. The console and instrument rack are in an air-conditioned enclosure for constant temperature and humidity control to protect sensitive instruments.

A covered trench in the floor runs the length of the experimental area at approximately the building center line. The trench leads to a sump outside the building along the west wall. The trench serves two purposes: drainage of spilled water to the sump, and concealment of piping and electrical conduits. The trench is designed to operate dry normally, but has the capacity to contain the total test loop water volume in the event of a spill.

## EXPERIMENTAL TEST STATIONS

The laboratory is arranged around three experimental test stations (A, B, and C in Figure 3) differing in capacity and purpose. The separate test stations provide for more-efficient use of power and flow equipment because test apparatus for one experiment does not need to be taken off line between tests to make way for tests with another apparatus for another study. Because time spent in setup and preparation for a test is considerably longer than the actual test time, sharing the power supply between stations is a negligible inconvenience.

The purpose of each of the three test stations is nominally as follows:

- A - Full size assembly testing
- B - Assembly flow instability
- C - Burnout heat flux measurements.

These functions can be interchanged among the test stations depending upon flow conditions required and the test section size.




FIG. 3 EQUIPMENT LAYOUT

## Test Station A

Test Station A (Figures 4,5) is for full size assembly tests involving assembly flow instability, end-fitting response to two-phase flow, steam injection into the moderator, and natural convection heat transfer in various types of reactor components. Test Station A is basically a tank, 3 feet in diameter, 20 feet high, capped by a pressurized inlet header (or plenum), and representing a mockup of a portion of an SRP reactor tank, with exact size plenum, permanent sleeves, and tank height. There are positions for 19 assemblies: 17 are "dummies" for a normal test, and two may be used for heated elements. The dummy positions can provide bypass flow around the test position to maintain an approximately constant hydraulic head across the test assembly.

Full pump flow (1200 gpm) can be supplied to the plenum. In addition, piping for a steam quench flow or secondary flow of up to 400 gpm is provided for the tank. Flow may be returned to pump suction either from the top of the tank or the bottom, depending upon the external cooling conditions to be imposed on the test section. The tank level is controlled automatically with a pneumatic system that regulates the water level by controlling air pressure in the space between tank water surface and plenum bottom.

Power for heating test sections may be introduced at the top above the plenum, or through ports in the side of the tank near the top and bottom. Six observation windows are located at three levels. Personnel access ports are also located at three levels to assist installation of test sections and instrumentation.

The two positions for heated test sections are provided with flow monitor pins at the tank bottom identical to those in SRP reactors so that instrument readings similar to those observed in the reactor may be obtained. Provision is also made in the tank wall for attaching pressure and temperature leads to the test sections for detailed measurements. End fittings are attached to the discharge ends of the test sections to develop signals for flow and temperature monitoring.

## Test Station B

Test Station B was designed to study internal assembly heat transfer and hydraulic characteristics, where the presence (and/or complication) of moderator cooling is not necessary. Typical testing includes flow instability, end-fitting characteristics, and multichannel hydraulic coupling with single phase and subcooled nucleate boiling flow.




FIG. 4. TEST STATION A PLAN




FIG. 5. TEST STATION A

Test Station B consists of a flanged inlet header located at elevation 23 feet and two return headers at the floor. Connections to the DC power supply are available at elevation 17 feet and the floor. Maximum flow is 1200 gpm at 220 psi with up to 400 gpm secondary or quench flow. Between the flanges of the inlet and return headers, test sections may be fitted that are limited only by the ingenuity of the experimenter. Figure 6 shows a typical test apparatus.

Instrumentation identical to that at Test Station A is available. Permanently installed pressure and thermocouple connections originating near test section inlet and return

header flanges lead to transducers and signal conditioners in the control enclosure. Flow may be bypassed through permanent system bypass piping to maintain constant head, or as in the arrangement shown in Figure 6, bypass features may be inherent in the test apparatus.




FIG. 6. TEST STATION B WITH TEST RIG IN PLACE

## Test Station C

Test Station C is designed primarily for burnout studies, although it is not limited to burnout tests. Compared to Test Station B, maximum flow is less and the test section size is smaller. Like Test Station B, Test Station C has the inlet and return process water flanges and the DC power bus connection points. Within the physical limits of the test station, any test section may be used. Figure 7 shows Test Station C with a typical test section installed. Inlet headers are 16.5 feet above the floor, and discharge headers are at the floor. Maximum flow is 400 gpm at 220 psi, with 90 gpm available as a secondary or quench flow. Pressure and temperature connections leading back to the control enclosure are installed at top and bottom of the test section.




FIG. 7. TEST STATION C WITH TEST RIG IN PLACE



## POWER SUPPLY

Electrical power is provided to the Heat Transfer Laboratory from the adjacent substation. The substation contains three 1500 kva transformers reducing line voltage from 13,800 volts to 460 volts. The 460 volt power is supplied to the rectifier units in the laboratory through overhead enclosed trays extending from the substation to the laboratory. Power for lights, pumps, instruments, and utilities passes to the laboratory through underground conduits to motor control centers, from which it is distributed.

### Rectifier Units

Direct current power is provided by six large solid state rectifiers connected in parallel (Figure 8). Each unit has a maximum rated output of 0.5 MW DC at 5000 amperes. Total capacity is 3 MW DC with all units on line. Depending upon test conditions, one or more units may be selected for use during a test.




FIG. 8. RECTIFIER UNITS

Figure 9 is a schematic of the rectification circuit. The wave shape of one phase at each stage is indicated. Three phase 460 volt AC power from the substation transformers first passes through silicon-controlled rectifiers (SCR), which are used to control total power. After the SCR's, the current is still alternating and is stepped down to a lower voltage by transformers in the rectifier cabinets. To minimize ripple, tapped transformers were used to enable operation near peak voltage with test sections of various impedances. The transformer secondary may be tapped at 30, 60, or 120 volts. For example, if the resistance of a test section were such that 30 volts was required at 5000 ampere operation, the waveform would be nearly pure DC if the 30 volt taps were used (i.e., ripple would be almost zero). However, if the 60 volt taps were used with the same load at 5000 amp, the waveform would have a high percent ripple, causing the power generation in the test section to fluctuate at the power frequency (360 Hz for three phase). Instrumentation, bubble formation, and other phenomena possibly critical to the experiment can be affected by this oscillating power.

Power is collected and distributed by bus bars made from 4 x 4 x 3/4 inch aluminum channel (Figure 10). The busses run the length of the experimental area: the positive bus is at 17 feet; the negative bus is in the trench. Connection blocks are provided for attachment of flexible connectors at each test station. Bus cooling is provided by water flowing through the center of the bus.




FIG. 9. SCHEMATIC OF RECTIFIER CIRCUIT




FIG. 10. CROSS SECTION OF BUS BARS

Connections are made to a test section by water-cooled flexible busses extending from the busses to copper adapter blocks appropriate for each test section. Cooling for the flexible connecting busses is provided from the bus cooling system.

Neither the positive nor negative bus is connected to the building electrical ground. This "floating" system was specified for the protection afforded personnel and equipment from an electrical short at high current. An apparatus may become grounded at one place to building ground (for example by contacting process water piping or rig framework) without a damaging arc because there is no path back to the second bus until a second ground occurs. Operating procedures prohibit startup with a grounded apparatus. A ground detection device alerts operators and shuts off the power when a ground occurs during a test. The necessity for two separate grounds before an arc or a shock hazard can exist enhances the system safety.

### Rectifier Controls

The rectifiers are monitored and operated from the control console. Rectifier units to be used are selected by appropriate switches. The output of the combined rectifiers is controlled by a single master control potentiometer. Power can be started and stopped with single start and stop buttons. At a given setting, the rectifiers hold the setpoint by internal feedback of voltage or current, the control variable being chosen by the operator. Rectifier power may also be programmed to follow any power-versus-time curve by feeding in an externally generated voltage signal describing the desired curve. This option can be used to simulate reactor power during postulated transients.

Each rectifier has an individual shunt for monitoring DC current. A voltmeter connected internally monitors the output voltage. Experimental power data is obtained with a specially constructed wattmeter which integrates the product of current and voltage, including any ripple, to obtain the exact DC heating value. Total current is obtained with a special measuring head sensitive to the magnetic field produced by the bus. Voltage is obtained by taps at top and bottom of the heated section. Voltage, current, and power are displayed by digital meters on the master control panel for quick reference. Power is also recorded on a chart recorder for permanent records. Accuracy of the power measurement is rated at 0.1% of the meter range selected. Meter ranges span from 0.3 to 3.6 MW in 6 intervals.

### COOLING WATER SYSTEM

A detailed schematic of the process water flow loops is shown in Figure 11. The intent of the design is to provide the three test stations with a choice of cooling supply:


<u>Max. Pumping Rate</u>	<u>Pipe Diam., in.</u>	<u>Test Station</u>
1200 gpm	6	A, B
200 gpm	2	A, B
400 gpm	3	A, B, C
170 gpm	1.5	A, B, C (Quench Flow)

Within these limits considerable latitude is possible, so that many combinations of primary coolant flow, quench or secondary flow, and test section pressure are possible at each station. Installed equipment includes:

- Three 400-gpm pumps at 400 ft H<sub>2</sub>O head
- One 90-gpm pump at 200 ft H<sub>2</sub>O head
- One 1000-gal calibration tank
- One 200-gal surge tank
- One 20-gal surge tank
- Two 600-ft<sup>2</sup> heat exchangers
- One 300-ft<sup>2</sup> heat exchanger
- Two 20-gpm deionizers

Control valves for pressure, temperature, and flow control  
Interconnecting piping

All process piping valves and tanks are stainless steel. The process cooling water header is galvanized steel pipe.



For clarity, Figure 12 is presented to illustrate cooling supply only to Test Station B. By appropriate valving, the other stations can be supplied in a similar manner. In Figure 12, primary coolant is supplied by one or more of the 400 gpm pumps in parallel. Inlet pressure and flow are adjusted by upstream valving and/or bypassing a part of the pump flow through a bypass line. Valves V4 and V14 have pneumatic operators controlled from the instrument panel. These valves also may be used to control automatically the test section pressure and flow. Excessive steam generated in the test section may be quenched by introducing flow from the 90 gpm pump system into the outlet plenum. This quench flow maintains the required net positive suction head for the pumps to prevent cavitation. Thus, two loops can be in operation simultaneously with independently controlled flow, temperature, and pressure.




FIG. 12. SCHEMATIC OF PIPING TO A SINGLE STATION

Primary flow is returned to the pumps through a large suction header via two heat exchangers arranged in parallel. The flow can bypass the heat exchangers or be partially admitted to the heat exchangers according to temperature control setpoints of the pneumatic control valves. Similarly, the quench flow is cooled by a smaller heat exchanger. The outlet temperature from this heat exchanger can also be held constant automatically by a controller and bypass valve. Various auxiliary manual valves are located to divert flow from one station to another and to isolate parts of the process system.

Process control instrumentation (which excludes special instrumentation associated with a particular test section) is available to monitor flow, pump suction temperature and pressure, and pump discharge pressure. Flow is measured by turbine meters in each of the flow loops, as shown in Figure 11. Four meters are available depending upon flow loop and flow rate. Nominal accuracy of these meters is within  $\pm 1\%$  over a range from 10% to 100% full scale. Flow meters are calibrated by draining water through the meters from the calibration tank. Conductivity level sensors are used to actuate a timer which measures the time required to discharge an accurately known volume through the meter. Pump discharge pressure is indicated by a Bourdon type 0-300 psi pressure gage. Pump suction pressures are given by lower range Bourdon gages.

Water in the process loops comes originally from deep wells on the Savannah River Plant site. After filling the loop, the water is deionized by periodic circulation through mixed bed deionizers. The calibration tank, the surge tank, and to some extent the Test Station A vessel serve as surge suppressors and head tanks for the pumps. Water level in each tank is indicated by differential pressure gages on the control panel.

## INSTRUMENTATION

Laboratory instrumentation may be divided generally into two groups: (1) instruments for process control and (2) instruments for acquisition of test data. Within each of these groups the instrumentation is split between recording-type units (e.g., chart recorders) and display type (e.g., Bourdon gages). There is some sharing of function in these divisions, where a process control variable, such as flow, may be used for process control and recorded as test data. As with the hydraulic loops, the instrumentation was designed to obtain versatility. Switch panels are provided to allow presentation of incoming signals on selected recording or display devices. In addition, terminals are provided for selecting signals leading to the console displays and feeding them to portable recording instruments.

Process control instrumentation was described in the preceding section. Electrical power instrumentation was discussed in the description of the rectifiers. Figure 13 is a photograph of the process control console showing digital display meters for monitoring temperatures, pressures, and rectifier power. Pump motor controls, valve controllers, and pressure gages are also shown at the far right. The consoles also contain some of the signal conditioning equipment and jack panels. Figure 14 shows permanently installed recording equipment for slowly changing variables. There are eight chart recorders: four two-pen recorders, one single-pen recorder, and three recorder controllers. Also shown in this photograph are the flow meter signal conditioning units and the rectifier selector panel. All recorders have a common off-on switch and special event marker triggered by the operator with a button on the main control console.

Portable recording equipment is also available, particularly for taking data involving fast transients. This includes multichannel oscillographic recorders, a digital recorder with up to 80 channels capable of recording 20 points per second on magnetic tape, and a high speed digital data acquisition system with 40 channels for recording up to 30,000 points per second on magnetic tape. An IBM 360/195 located in the Savannah River Laboratory is available for data reduction and analysis. Provision has been made for installation of a remote computer terminal in the heat transfer laboratory building.




FIG. 13. CONTROL CONSOLE






FIG. 14. RECORDER CONSOLE